



## About San Diego (SD01-Koll)

Our portfolio includes 31 Data Centers across 4 continents, 11 countries and 25 markets. Our centers are designed to deliver high standards of reliability including redundant power, cooling and dual rail connectivity and have historically met or exceeded 99.999 percent availability. With over 18 years of data center operational experience and our commitment to excellence you can be confident in selecting Evoque Data Center Solutions™ as your colocation partner.

### LOCATION

5732 Pacific Center Boulevard San Diego, CA 92121

**From Airport:** 17 miles\* from San Diego International Airport

**Location:** 2.5 miles\* to the I-805 & I-5 Freeway split

**Distance to Hawthorne IDC:** 110 miles\*

**Parking:** On site parking

\*approximate mileage



### PROFILE

**Data Center**  
 Overall: 68,600 sq. ft.  
 Colocation: 40,600 sq. ft.  
 Office Space: Customer drop in cubicles  
 Site: 2-story  
 Site Area: Multi-tenant  
 Seismic Zone: 4  
 Built: 1982  
 Retrofitted: 1999

**Amenities**  
 Customer Lounge: Yes  
 Conference Room: Yes

**Telco Information**  
 NPA / NXX: 858 / 450  
 CLLI Code: SNDKCACN  
 POP: SNDGCA02  
 Carriers: ATT LNS, SBC, Level 3

### COOLING

**HVAC Distribution:** N+1  
**HVAC System:** N+1  
**Chillers:** Building A has three 230 Ton air cooled chillers. Building B has four 180 Ton air cooled chillers.

### NETWORK

**Internet:** 100 GB Ethernet WAN uplinks to the ATT IP Network  
**Redundancy:** Redundant and path-diverse entrances and exits

### PHYSICAL SECURITY

**Physical:** Mantrap  
**Staffing:** 24x7  
**Electronic:** Closed circuit monitors, secure key-card access, biometrics scanner, and alarmed doors

### BUILD OUT

**Types:** Cage, locking cabinets  
**Standard Rack:** 42U  
**Raised Floor Load:** None  
**Sub Floor Load:** 300 lbs. / sq. ft.  
**Cross Connect:** Copper, fiber, coaxial  
**Remote Hands:** 24x7  
**Loading Dock:** Yes

### FIRE PROTECTION

**Fire Alarm:** VESDA Smoke Detection and Conventional Addressable Fire Alarm System  
**Fire Suppression**  
**Data Center Areas:** Pre-action dry pipe  
**Non-Equipment Areas:** Wet sprinkler

### POWER

**Electrical Capacity**  
 Bldg. A 150 w/ sq. ft.  
 Bldg. B 150 w/ sq. ft.  
 Cabinet (2.4, 4.3 & 6.2 Kw)  
**UPS Configuration:** 2N  
**# Utility Feeders:** 2  
**Standby Power Config:** N+1  
**Standby Power:** Bldg. A has three 1,500 kW diesel generators.  
 \*\*\*Building A generator #3 is a swing engine and can be used for Building B if needed \*\*\*  
 Bldg. B has two 1,600 kw diesel generators; two 16,000 gallon above ground fuel tanks.

### SLA

Services historically meet or exceed 99.999% availability

### AUDIT / CERT. STANDARDS

•SSAE 16 •ISO 27001 •PCI v3.2